

**GOVERNMENT OF KERALA**  
**Agriculture Department**

O/o, State Agricultural Engineer,  
Directorate of Agriculture

No :AGRI/DOA/22/2024-2025

Dated :10-07-2024

**NOTICE INVITING TENDER**

**e-Government Procurement (e-GP)**

**TENDER NO. :AGRI/DOA/TR/69/2024\_5\_1\_1/2**

The State Agricultural Engineer Agriculture Department, (AGRI)O/o Office of the State Agricultural Engineer ,Directorate of Agriculturefor and on behalf of the Governor of Kerala invitesonline bids for the work detailed below from the Registered Bidders of Kerala PWD or from any State or Central Government Engineering Departments which are having similar functionalities like Kerala PWD.

1	Name of Work	NABARD--RIDF XXIX Infrastructural development works at various padasekharams of Cherthala LAC Part3-Thanneermukkam panchayath-Thanneermukkam panchayath-General Civil Work
2	Location of Work	Alappuzha
3	Estimated Cost of Work	Rs.28196497/-

4	Brief Description of Work	<p>Appendix -1Thaneermukkom - Pothimangalam Padam - Construction of Sluice Earth work excavation for sluice .Supplying and piling full log coconut log for foundation and DR packing above the above them. Laying PCC 1:4:8 using 40mm b/s as basement above that DRM for foundation .Providing and laying RCC 1:2:4 using 20mm b/s for base slab, abutment and pier. Provision for foot slab using RCC 1:2:4 using 20mm b/s. Provision for shutter using Anjiliwood .All the details of length, breadth and height etc mentioned in the detailed estimate</p> <p>Appendix - 2Thaneermukkom - Puncha Padam - Side protection work Earth work excavation for side protection work. DRM for foundation and super structure and PCC 1:3:6using 20mm b/ for wearing coat.The details of length ,breadth and height mentioned in the detailed estimate</p> <p>Appendix - 3Thaneermukkom - Puncha Padam &amp; Kakkathurthu padam - Construction of Sluice Earth work excavation for sluice .Supplying and piling full log coconut log for foundation and DR packing above the above them. Laying PCC 1:4:8 using 40mm b/s as basement above that DRM for foundation .Providing and laying RCC 1:2:4 using 20mm b/s for base slab, abutment and pier. Provision for foot slab using RCC 1:2:4 using 20mm b/s. Provision for shutter using Anjiliwood .All the details of length, breadth and height etc mentioned in the detailed estimate</p> <p>Appendix - 4Thaneermukkom - Pothimangalam padam - Side protection work Earth work excavation for side protection work. DRM for foundation and super structure and PCC 1:3:6using 20mm b/ for wearing coat.The details of length ,breadth and height mentioned in the detailed estimate</p> <p>Appendix - 5Thaneermukkom - Kakkathurthu padam Padam - Construction of Culvert &amp; Ramp Earth work excavation for Culvert. DRM for foundation and PCC 1:4:8 using 40mm b/s as base concrete. .Providing and laying RCC 1:2:4 using 20mm b/s for base slab, abutment and pier and top slab. Earth work excavation for sides of Ramp and DRM for foundation and super structure for RRM .Providing DR packing inside the ramp.PCC 1:4:8 using 40mm b/s above DR packing and above that RCC 1:2:4 using 20mm b/s. The details of length ,breadth and height mentioned in the detailed estimate.</p> <p>Appendix - 6Thaneermukkom - Kakkathurthu padam Padam - Construction of sump Earth work excavation for foundation of sump and DR packing above the above them. Laying PCC 1:4:8 using 40mm b/s above DR packing and above that RCC 1:2:4 using 20mm b/s for base slab ,side wall etc providing. All the details of length, breadth and height etc mentioned in the detailed estimate</p> <p>Appendix - 7Thaneermukkom - Pothimangalam &amp; Kakkathurthu padam - Shutter for sluice Provision for shutter the existing sluice using Anjiliwood</p> <p>Appendix - 8Thaneermukkom - Pothimangalam padam - Renovation of seed store Demolishing the existing damaged concrete floor and laying PCC 1:4:8 using 40mm b/s and above that PCC 1:2:4 using 20mm b/s. dismantling the damaged roofing sheet ,supplying and fixing new GI sheet.</p>
---	---------------------------	---

		Appendix - 9Thaneermukkom- Kakkathurthupadam Padam - Construction of Retaining wall Earth work excavation for side protection work. DRM for foundation and super structure and PCC 1:3:6 using 20m m b/s for wearing coat. The details of length, breadth and height mentioned in the detailed estimate
5	Bid Security	Rs.100000/-
6	Bid Submission fee (Tender fee)	8270+(1489)GST
7	Period Of Completion	0 Days 6 Months 1 Years
8	Classification of Bidder	CIVIL-A
9	Last date and time for submission of bids	27-07-2024 at 15:00
10	Date and time of opening of tender	29-07-2024 at 14:00

Bid documents including the Bill of Quantities (BoQ) can be downloaded free of cost from the e-Government Procurement (e-GP) Website [www.etenders.kerala.gov.in](http://www.etenders.kerala.gov.in). All bid documents are to be submitted online only and in the designated cover(s)/ envelope(s) on the e-GP website. Tenders/ bids shall be accepted only through online mode on the e-GP website and no manual submission of the same shall be entertained. Late tenders will not be accepted. A bid submission fee shall be remitted online during the time of bid submission.

Price Bid shall only be submitted through online. Details regarding remittance of Bid Submission Fee and Bid Security, Bid preparation and submission are mentioned in the bid document.

The bids shall be opened online on 29-07-2024 at 14:00 at the office of the O/o Office of the State Agricultural Engineer, Directorate of Agriculture in the presence of the Bidders /their authorized representatives who wish to attend at the above address. If the tender opening date happens to be on a holiday or non-working day due to any other valid reason, the tender opening process will be done on the next working day at same time and place.

More details can be had from the Office of the State Agricultural Engineer, Agriculture Department (Agriculture Department) O/o Office of the State Agricultural Engineer, Directorate of Agriculture during working hours.

All other existing conditions related to bidding in force in the Kerala Public Works Department will be applicable in this tender also unless expressly defined in the bidding document. The Tender Inviting Authority/Employer shall not be responsible for any failure, malfunction or breakdown of the electronic system while downloading or uploading the documents by the Bidder during the e-procurement process. Details required for e-payment (Details of bank account having core banking facility and email address of the bidder) shall be furnished along with the tender. Tenders not accompanied by these details will be rejected. All subsequent Government orders connected to tenders and any revision in the rates of taxes would also be applicable to this tender.

Bonus will be paid to the bidder at the rate of 1% of the estimated PAC, subjected to a maximum of Rs.5 lakhs (Five lakhs) in case of works which exceed TS power of Superintending Engineer and also if and only if the work is completed within 85% of the original time of completion (TOC) specified in the TS estimate which is calculated as per the guidelines issued by the Chief Engineer of each wing.

The State Agricultural Engineer, Agriculture Department (AGRI), O/o Office of the State Agricultural Engineer , Directorate of Agriculture reserves the right to accept or reject any or all tenders without assigning any reason thereof.

**State Agricultural Engineer**

Agriculture Department(AGRI)

**O/o Office of the State Agricultural Engineer,  
Directorate of Agriculture  
(For and on behalf of Governor of Kerala)**

